

Name		

Date

Renovation Estimates

1. Front yard below stone retaining wall, left and right of front walk:


Area: 854 square feet

Soil: Till and amend soil with 1.75" compost and lime Plant:

Creeping Red Fescue

Mulch: Wheat straw

Irrigation: Establish watering system Materials and Labor: \$723



Area: 576 square feet

Soil: Till and amend soil with 1.5" compost and lime Plant: Liriope

Mulch: 3" double ground hardwood Irrigation: Establish watering system

Materials and Labor: \$525

3. Foundation Beds, left and right of front door: Area: 400 square feet

Soil: Till and amend soil with 2.25" compost and lime

Plant: Boxwood, 12 at 7 gallon size plants, and 18 at 3 gallon size

plants Mulch: 2" double ground hardwood

Materials and Labor: \$1266

4. Border bed above the stone wall and

driveway: Area: 80 feet length, 380 square feet

Soil: Till and amend soil with 2.25" compost and

lime Plant: Vinca Minor

Mulch: 2" double ground

This document and its content is protected under copyrights laws and owned solely by ReadTheory Limited Partnership; Distributing, reusing, republishing the document in any way or form is forbidden.





hardwood Materials and Labor:

\$355

Schedule of Services:

Work is expected to commence: Wednesday, July 13

Work is expected to be completed: Wednesday, July 27, barring any unforeseen circumstances

This contract can be reviewed at any time by either party and shall be in effect until satisfactory completion of the project(s). Changes in contract specifics must be provided as written amendments to this contract with the signature approval of both parties.